



**F.No. AEPC/HO/AHM/204/2018**

**Notice inviting Quotation**

**28<sup>th</sup> May, 2018**

Sealed bids are invited from reputed contractors/firms for repairing of our exterior floor tiles along with minor electrical and carpentry work. The scope of work is also attached with tentative quantity.

. You are requested to visit the site by 29.05.2018 and assess the same for yourself and send in your best rates by 30.05.2018 by 3 pm

Please also note the following:

1. The quote should be accompanied with an EMD of Rs. 50,000/-
2. The agency finalised shall deposit 5% as security deposit towards performance guarantee.
3. The defect liability period shall be 1 year
4. You are requested to quote category wise for unit rate against the approximate quantity of work description. The final assessment shall be made on actual measurement basis. For e.g: You are to quote unit rate separately for carpentry work, painting work, electrical work , civil work etc.

**(J.S. Rana)**

Jt. Director (AHM)

Apparel Export Promotion Council

Gurgaon-122003, Haryana

0124-2708191

<b>Proposed estimate for Civil repair work at Apparel house Sector 44 Gurgaon.</b>					
<b>Sn</b>	<b>Description</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount</b>
	<b>CIVIL</b>				
1.1	Removing of existing skirting & nearby kota stone flooring / other areas and providing / applying / pouring of slurry prepared with cement and water providing chemical (1 ltr. Per 1 bag of cement bag) to make complete water proof at few locations and re-fixing the same.	Sqm.	662.69		
1.2	Italian marble Flooring and Skirting : With 18-20mm thick diamond polish machine cut Perlato and dark emperador over 20mm (average) thick base of cement mortar 1:4 (1 cement :4 coarse sand) followed by laying and fixing with highly polymer single component adhesive of LATICRETE / BAL ENDURA or equivalent with minimum 6 mm thickness and jointed with white cement slurry mixed with matching pigment, including rubbing and polishing and curing etc. complete at all levels or injection moulding as directed.	Sqm	40.18		
1.3	Dismantling Pavear block in floors and roofs laid in cement mortar including stacking material within any lead.				
	For thickness of pavear tiles 80 mm to 100 mm	Sqm.	50.51		
1.4	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) :				
	25 mm thick	Sqm	278.89		
1.5	Labour charges for fixing of interlockoing paver block with required material.(Only pavear supplied by Client)	Sqm	224.51		
1.6	Supply & placing in position as per approved pattern of cement concrete interlocking /grass jointed paver block 60 mm thick of approved shape,rough finish,M30 strength of approved brand laid over the sand bed of minimum 100 mm thick. The CC interlocking block to be as approved by EIC complete.Item includes cartage , taxes, overhead & contractor profit complete.	Sqm	60		

2	<b>ELECTRICAL</b>				
2.1	Repair of electrical points and relaying of electrical wires in proper conduits along the plaza area	No.s.	15		
3	<b>PAINTING</b>				
3.1	Removing of exterior texture paint by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete for Exhibition Hall area only	Sqm.	6000		
3.2	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	Cum.	15.00		
3.3	Providing and applying three coats of pre-approved Plastic acrylic emulsion paint to walls, partitions etc. including surface preparation with two coats of putty, primer and sanding all complete. With the necessary drying periods for each coat. Cost to be inculde for all heifht and surfaces.(Low VOC contain paint) Make: ICI DULUX ,Asian Paints . <b>Area shall be exhibition Hall Area only</b>	Sqm	6000		
3.4	Finishing walls with Acrylic Smooth exterior paint of required shade-(Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)as approved by EIC.Item includes cartage , taxes, overhead & contractor profit complete.	Sqm	4000		

3.5	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as approved by EIC.Item includes cartage , taxes,	Sqm	4500		
4	<b>CARPENTRY</b>				
4.1	Repairing of Teak wood batten door frame by replacement for termite infected door frame battens similar to existing frame design & pattern & thickness complete.	Each	10.00		
4.2	Providing and fixing 2nd class teak wood 50x12 mm wooden moulded beading to door and window frames with iron screws, plugs and priming coat on unexposed surface etc.	M	80		
4.3	Extra for providing and fixing 1 mm thk. laminate of approved shade and design-On one side as approved by EIC.Item includes cartage , taxes, overhead & contractor profit complete.	Sqm	8		
4.4	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:- 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws as approved by Engineer in charge.Item includes cartage , taxes, overhead & contractor profit complete.	Sqm	17.90		